

Materials List

ITEM	QTY.	ITEM	QTY.	ITEM	QTY.
80-lb. bags of concrete mix	10	2x8 x 16' SPF gussets	1	4' aluminum screening	150 ft.
6x6 x 4' .60 treated posts	5	2x8 x 16' SPF truss blocking	2	36" screen door	1
2x10 x 14' treated joists, blocking	17	2x8 x 8' SPF tie-in ridge	1	Post brackets	5
5/4x6 x 14' cedar decking	28	2x8 x 10' SPF tie-in plates	2	Double inverted-flange beam hangers	2
2x4 x 14' cedar plates, crosspieces and gable end*	14	2x6 x 10' SPF tie-in rafters	1	2x10 joist hangers	18
2x2 x 14' cedar screen covers*	14	1x2 x 8' SPF truss furring	2	Joist hanger nails	5 lbs.
2x4 x 8' cedar uprights*	21	2x10 x 14' SPF or cedar trim board	2	16d double-dipped galvanized nails	5 lbs.
2x2 x 8' cedar screen covers*	21	2x10 x 16' SPF or cedar trim board	1	12d galvanized box nails	5 lbs.
2x2 x 14' gable end frame	2	4x8 x 3/4" CDX plywood	2	3/8" x 4" galvanized lag screws	22
2x4 x 14' cedar (rip for sill)	2	2x6 x 16' tongue-and-groove cedar	46	2-5/8" deck screws	6 lbs.
2x4 x 16' cedar (rip for sill)	1	1x3 x 12' cedar trim	2	3" weather-resistant deck screws	5 lbs.
2x6 x 8' cedar corner boards	4	1x3 x 16' cedar trim	2	1/2" x 5-1/2" galvanized carriage bolts, nuts and washers	20
2x4 x 16' SPF (spruce, pine or fir) bracing	5	1x6 tongue-and-groove cedar	48 ft.	1" galvanized roofing nails	10 lbs.
1x4 x 16' roof brace	1	Ice and water membrane	300 s.f.	5/16" staples	1 box
2x8 x 12' SPF rafters	22	No. 15 building paper	400 s.f.	2-1/2" screen door hinges	3
2x6 x 16' SPF crossties	5	Shingles	400 s.f.	Screen door closer	1
		10' lengths of metal drip edge	5	Screen door latch	1
		10' lengths of valley flashing	3		

* Option: Rip these pieces from 2x6s.